





1150 CLEMENT RD  
PARIS, TX 75460

# Estimate

Date	Estimate #
8/3/2017	4726

Name / Address
hOPKINS COUNTY SHERIFF

Project
FREEZER WITH 2 SYST...

Item	Description	Qty	U/M	Rate	Total
	crankcase heater, compressor contactor, high/low pressure control, receiver, liquid filter/drier/sight glass/moisture indicator, evaporator, expansion valve, solenoid valve. thermostat is shipped loose. refrigerant r404a RFO400L4S-G -1-AE36-140C-FP Entering Product- Beef And Produce Entering Temp- 75° Holding Temp- -10° Ambient- 110° 2 2 Extended 2nd-5th year refrigeration warranty 3 1/2 to 4 hp compressor only crhcus-052-4p (3341) Price - \$378.31 Per Unit. Included in total price. Test assembly, packaging, and handling - 3'4" x 8'6" x 5' vertical skid 8 - 57" uprights & 2 - 40"bottom boards 1 Test assembly, packaging, and handling - 4' x 11' x 7' flat stack skid ltl Includes 4 pieces of full wrap fiber corners. 1				
LABOR	LABOR	1.00		4,200.00	4,200.00
MATERIALS	COPPER ,FITTING, ARMOFLEX,STUT CLAMPS ALL THREAD ,MISC SEALING TAPE ,MP ONE SEALANT	1.00		854.40	854.40
R-404A	FREON	32.00	LB	13.56	433.92
WELD-LARGE	LARGE WELDING CHARGE	1.00		75.00	75.00
MILEAGE-SS	MILEAGE TO SULPHUR SPRINGS	3.00		43.32	129.96
S2448EPS	24"X48" WIRE SHELF, EPOXY PLATINUM SILVER	20.00	EA	31.88	637.60

**Subtotal**

**Sales Tax (8.25%)**

**Total**

Acceptance



1150 CLEMENT RD  
PARIS, TX 75460

# Estimate

Date	Estimate #
8/3/2017	4726

Name / Address
hOPKINS COUNTY SHERIFF

Project
FREEZER WITH 2 SYST...

Item	Description	Qty	U/M	Rate	Total
EQUIPMENT	<p>WALKIN FREEZER BID 2</p> <p>Description Rain roof, single membrane polyester polyvinyl chloride roof system with connectors &amp; drip cap for door. White Material. (usc 643) Actual length: 20'-0" Actual width: 11'-0"; Freestanding TermBar:70 Plate:40 Screw:180 Caulk:0 1 Walk-In Freezer: 19'-0" X 10'-0" X 7'-6" - 4" extruded polystyrene, stucco embossed galvalume 26 gauge exterior, stucco embossed galvalume 26 gauge interior, nsf approved. 1 Floor: 19ft. 0in. X 10ft. 0in. - 4" extruded insulation, 22 gauge stainless steel interior, stucco embossed galvalume 26 gauge exterior U.S. Cooler floors are not designed for the use of Forklifts, Pallet Jacks, or Hard Wheeled Carts. Damage caused by this usage will void the panel warranty 1 Door, 34 in. X 76 in.; low temp outside, with floor, threshold. Vert-Ergo handle, LED light, LED thermometer switch, door closure and adjustable spring-loaded hinges, drip cap and screws., hinge left centered on left width wall , with U.S. Cooler Logo 1 1 Pressure relief (usc 9644) installed 2 Non-charged preassembled low temp system 4 hp, 3 phase, 460V includes; Scroll compressor, weatherhood,</p>	1.00		26,986.66	26,986.66
				<b>Subtotal</b>	
				<b>Sales Tax (8.25%)</b>	
				<b>Total</b>	

Acceptance



1150 CLEMENT RD  
PARIS, TX 75460

# Estimate

Date	Estimate #
8/3/2017	4726

Name / Address
hOPKINS COUNTY SHERIFF

Project
FREEZER WITH 2 SYST...

Item	Description	Qty	U/M	Rate	Total
S2460EPS	24"X60" WIRE SHELF, EPOXY PLATINUM SILVER	20.00	EA	38.75	775.00
P74EPS	74" EPOXY POST	40.00	EA	11.25	450.00
MISC	RED LITE WITH THERMOSTATE FOR EMERGENCY ALARM	1.00		154.00	154.00
MISC	BID FROM BOBBY HARRIS INCLUDES MATERIAL /LABOR AND LIGHTS	1.00		4,500.00	4,500.00
				<b>Subtotal</b>	\$39,196.54
				<b>Sales Tax (8.25%)</b>	\$0.00
				<b>Total</b>	\$39,196.54

Acceptance \_\_\_\_\_